# SITE DEVELOPMENT PLANS

- TAX MAP 249, LOT 16


# All Purpose Storage - Boat & RV

HALL ROAD

CANTERBURY, NEW HAMPSHIRE

MAY 24, 2022

LAST REVISED: JUNE 4, 2024



### WILDLIFE PROTECTION NOTES (PER ENV-WQ 1504.18):


- ALL OBSERVATIONS OF THREATENED OR ENDANGERED SPECIES SHALL BE REPORTED IMMEDIATELY TO THE NEW HAMPSHIRE FISH AND GAME DEPARTMENT NONGAME AND ENDANGERED WILDLIFE ENVIRONMENTAL REVIEW PROGRAM BY PHONE AT 603-271-2461 AND BY EMAIL AT NHFGreview@WILDLIFE.NH.GOV. EMAIL SUBJECT LINE: NHB22-3428, ALL PURPOSE STORAGE CANTERBURY, WILDLIFE SPECIES
- PHOTOGRAPHS OF THE OBSERVED SPECIES AND NEARBY ELEMENTS OF HABITAT OR AREAS OF LAND DISTURBANCE SHALL BE PROVIDED TO NHF&G IN DIGITAL FORMAT AT THE ABOVE EMAIL ADDRESS FOR VERIFICATION AS FEASIBLE.
- IN THE EVENT A THREATENED OR ENDANGERED SPECIES IS OBSERVED ON THE PROJECT SITE DURING THE TERM OF THE PERMIT, THE SPECIES SHALL NOT BE DISTURBED, HANDLED, OR HARMED IN ANY WAY PRIOR TO CONSULTATION WITH NHF&G AND IMPLEMENTATION OF CORRECTIVE ACTIONS RECOMMENDED BY NHF&G, IF ANY, TO ASSURE THE PROJECT DOES NOT APPRECIABLY JEOPARDIZE THE CONTINUED EXISTENCE OF THREATENED AND ENDANGERED SPECIES AS DEFINED IN FIS 1002.04.
- THE NHF&G, INCLUDING ITS EMPLOYEES AND AUTHORIZED AGENTS, SHALL HAVE ACCESS TO THE PROPERTY DURING THE TERM OF THE ALTERATION OF TERRAIN PERMIT.

# ENGINEER CERTIFICATION (PER ENV-WQ 1503.21(c)):

- THE PERMIT HOLDER SHALL HAVE A QUALIFIED ENGINEER CERTIFY THAT THE PROJECT WAS CONSTRUCTED IN ACCORDANCE WITH THE APPROVED PLANS, OR THAT DEVIATIONS WERE MADE WHICH DID NOT REQUIRE AN AMENDED OR NEW PERMIT WITH THE NHDES ALTERATION OF TERRAIN BUREAU.

## WETLAND CERTIFICATION:

NO JURISDICTIONAL WETLANDS WERE OBSERVED DURING A SITE INSPECTION CONDUCTED BY KENNETH M. ROBINSON, CWS IN APRIL 2022 IN ACCORDANCE WITH THE "CORPS OF ENGINEERS WETLAND DELINEATION MANUAL, TECHNICAL REPORT Y-87-1, DATED JANUARY 1987 AND REGIONAL SUPPLEMENTS FOR NORTHEAST AND NORTHCENTRAL REGION AND FIELD INDICATORS FOR HYDRIC SOILS IN NEW ENGLAND".




- 1. THE LOCATION OF THE UTILITIES SHOWN ARE APPROXIMATE. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO LOCATE AND PRESERVE ALL UTILITY SERVICES.
- 2. THE CONTRACTOR IS RESPONSIBLE FOR CONTACTING AND COORDINATING WITH ALL UTILITY COMPANIES AND JURISDICTIONAL AGENCIES PRIOR TO AND DURING CONSTRUCTION.
- THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS
   AND PROPOSED WORK PRIOR TO CONSTRUCTION.

contact dig safe
72 Hours Prior
TO CONSTRUCTION

DIGSAFE.COM

811



# SHEET INDEX PAGE SHEET TITLE 1 CV-1 COVER SHEET 2 SP-1 SITE LAYOUT PLAN 3 EX-1 EXISTING CONDITIONS PLAN 4 GR-1 GRADING & DRAINAGE PLAN 5 LT-1 LIGHTING PLAN 6 LS-1 LANDSCAPING & UTILITIES PLAN 7 DT-1 EROSION CONTROL DETAILS 8 DT-2 CONSTRUCTION DETAILS 9 DT-3 CONSTRUCTION DETAILS

# PREPARED FOR & LAND OF. PATRIOT HOLDNGS, LLC

4007 DEAN MARTIN DRIVE LAS VEGAS, NV 89103-4138






APPROVAL:										
THE	SITE	PLAN	RE	GULAT	rions	OF	THE	TOWN	OF	CANTERB
INCC	PPAR	ATEN	RΥ	REFE	RENCI	- ΔC	: PAI	RT OF	THE	APPROV


INCORPORATED BY REFERENCE AS PART OF THE APPROVAL OF THIS PLAN.


THIS SITE PLAN IS HEREBY APPROVED BY THE PLANNING BOARD AT AN OFFICIAL MEETING HELD ON


DATE CHAIRMAIN OF THE PLANNING BOARD


PARTICIPATE CONTRACTOR TO THE PARTICIPATE OF THE PA	THE PERSON NAMED IN COLUMN TWO IS NOT THE OWNER.	P\$-17 HOME TO STATE OF THE WAY TO STATE OF THE PARTY OF T				termalistanten over segarantse	entertorphonic proces	*****	THE PERSON NAMED OF THE PERSON NAMED IN	ş
С	6/4/24		SITE PLAN	I AMENDMEN	١T			JEN	CEB	
В	12/15/22		AOT RMI	SUBMISSIO	И			JEN	CEB	
Α	11/2/22		AOT S	UBMISSION				JEN	CEB	1
REV.	DATE	nen marrodrikkum audook IV innistativõusidatta viika ja vasta	DES	CRIPTION		103 1704 S240 MPH (T245 And MOST	C/0	DR	CK /	
FILE: 31	27CV01C.dwg	PROJ. NO.	3127.01	SHEET:	CV-1	PAGE N	0. 1 (	)F 9		











- PRIOR TO STARTING ANY WORK ON THE SITE THE CONTRACTOR SHALL NOTIFY APPROPRIATE AGENCIES.
- 2. ALL SOIL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE IN ACCORDANCE WITH STANDARDS AND SPECIFICATIONS THEREOF IN NEW HAMPSHIRE DEPARTMENT OF ENVIRONMENTAL SERVICE STORM WATER MANUALS. VOLUME 1-3, LATEST EDITION.
- 3. EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE INSTALLED PER PLANS AND DETAILS. PERIMETER CONTROLS SHALL BE IN PLACE PRIOR TO COMMENCEMENT OF EARTH DISTURBING ACTIVITIES.
- 4. INSTALL INLET PROTECTION AROUND ALL STORM DRAIN STRUCTURES. INLET PROTECTION BMP'S SHALL REMAIN UNTIL THE SITE IS STABILIZED. CONSTRUCTION OF STORMWATER BASINS AND TREATMENT SWALES SHALL OCCUR PRIOR TO AND EARTH MOVING OPERATION THAT WILL INFLUENCE STORM WATER RUNOFF.
- THE WORK AREA SHALL BE GRADED, SHAPED AND OTHERWISE DRAINED IN SUCH A MANNER AS TO MINIMIZE SCIL EROSION, SILTATION OF DRAINAGE CHANNELS, DAMAGE TO EXISTING VEGETATION, AND DAMAGE TO PROPERTY OUTSIDE THE LIMITS OF THE WORK AREA.
- 6. EXISTING VEGETATION IS TO REMAIN UNDISTURBED WHEN POSSIBLE.
- EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE KEPT CLEAN DURING CONSTRUCTION. EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE INSPECTED AT LEAST ONCE A WEEK AND AFTER EVERY 0.25-INCH OR GREATER RAINFALL. SEDIMENTS SHALL BE DISPOSED OF IN AN UPLAND AREA THAT WILL NOT CONTRIBUTE TO SEDIMENT OFF—SITE AND BE PERMANENTLY STABILIZED.
- 8. THE SMALLEST PRACTICAL AREA SHALL BE DISTURBED DURING CONSTRUCTION. AT NO TIME SHALL THE TOTAL UNSTABILIZED DISTURBED AREA, INCLUDING LOT DISTURBANCES, BE GREATER THAN FIVE (5) ACRES.
- 9. THE LAND AREA EXPOSED SHALL BE KEPT TO THE SHORTEST PRACTICAL PERIOD OF TIME. ALL NON-ACTIVE DISTURBED AREAS SHALL BE STABILIZED WITHIN 30 DAYS OF THE DISTURBANCE. ALL DISTURBED AREAS SHALL BE STABILIZED WITHIN 72 HOURS OF FINAL GRADING.
- 10. DITCHES, SWALES AND DRAINAGE BASINS SHALL BE CONSTRUCTED DURING THE INITIAL PHASE OF CONSTRUCTION AND STABILIZED PRIOR TO DIRECTING RUNOFF TO THEM.
- 11. AN AREA SHALL BE CONSIDERED STABILIZED IF ONE OF THE FOLLOWING HAS OCCURRED:
- A. BASE COURSE GRAVELS HAVE BEEN INSTALLED IN AREAS TO BE PAVED: B. A MINIMUM OF 85% VEGETATED GROWTH HAS BEEN ESTABLISHED;
- C. A MINIMUM OF 3-INCHES OF NON-EROSIVE MATERIAL, SUCH AS STONE OR RIPRAP, HAS BEEN INSTALLED; OR
- D. EROSION CONTROL BLANKETS HAVE BEEN PROPERLY INSTALLED.
- 12. EROSION CONTROL BLANKETS SHALL BE INSTALLED ON ALL SLOPES THAT ARE STEEPER THAN 3:1 (HORIZONTAL / VERTICAL). UNLESS OTHERWISE SPECIFIED THE CONTRACTOR SHALL USE NORTH AMERICAN GREEN SC150, OR
- 13. ALL AREAS RECEIVING EROSION CONTROL STONE OR RIPRAP SHALL HAVE A GEOTEXTILE MATERIAL INSTALLED BELOW THE STONE (SEE APPROPRIATE DETAILS).
- 14. ALL DISTURBED AREAS TO TURF FINISHED SHALL BE COVERED WITH A MINIMUM THICKNESS OF 6 INCHES OF COMPACTED LOAM. LOAM SHALL BE COVERED WITH THE APPROPRIATE SEED MIXTURE AS INDICATED BELOW: PERMANENT SEED (LAWN AREAS) LRS / 1,000 SO ET | PERMANENT SLOPE SEED MIX LRS / 1,000 SO ET

PERMANENI SEED (LANN AREAS)	LDS / 1,000 SQ. FI.	PERMANENT SECT MIX	TR2 \ 1'000 20' L
CREEPING RED FESCUE PERENNIAL RYEGRASS KENTUCKY BLUEGRASS REDTOP	0.92 LBS 1.15 LBS 0.58 LBS 0.12 LBS	CREEPING RED FESCUE PERENNIAL RYEGRASS REDTOP ALSIKE CLOVER BIRDSFOOT TREFOIL	0.80 LBS 0.69 LBS 0.12 LBS 0.12 LBS
**APPLICATION RATE TO	OTALS	**APPLICATION	RATE TOTALS

\*1.85 LBS PER 1,000 SF\*\*

SHOWN ON PLAN OR AS NEEDED

DT-1

- 15. TEMPORARY STABILIZATION OF DISTURBED AREAS: STRIPPED SOIL SHALL BE STOCKPILED UNCOMPACTED, AND STABILIZED AGAINST EROSION AS OUTLINED BELOW: SEED BED PREPARATION: 10-10-10 FERTILIZATION TO BE SPREAD AT THE RATE OF 7 LBS. PER 100 SF AND AGRICULTURAL LIMESTONE AT A RATE OF 90 LBS PER 1000 SF AND INCORPORATED INTO THE SOIL. THE SOIL, FERTILIZER AND LIMESTONE SHALL BE TILLED TO PREPARE FOR SEEDING.
- A. SEED MIXTURE: USE ANY OF THE FOLLOWING:

2.8 LBS PER 1,000 SF\*\*

SPECIES	RATE PER 1,000 SF	<u>DEPTH</u>	SEEDING DATES
WINTER RYE	2.5 LBS	1 INCH	8/15 TO 9/15
OATS	2.5 LBS	1 INCH	4/15 TO 10/15
ANNUAL RYEGRASS	1.0 LBS	0.25 INCH	8/15 TO 9/15

B. MULCHING: MULCH SHOULD BE USED ON HIGHLY ERODIBLE AREAS, AND WHERE CONSERVATION OF MOISTURE WILL FACILITATE PLANT ESTABLISHMENT AS FOLLOWS:

. 10 ==	TOWN CONDENSIONS TO THE	LONG.	
	TYPE	RATE PER 1,000 SF	USE AND COMMENTS
	STRAW	70 TO 90 LBS	MAY BE USED WITH PLANTINGS, MUST BE ANCHORED TO BE USED ALONE
	WOOD CHIPS OR BARK MULCH	460 TO 920 LBS	USED WITH TREE AND SHRUB PLANTINGS
	FIBROUS MATTING	AS RECOMMENDED BY MANUFACTURER	MUST BE BIODEGRADABLE. USE IN SLOPE AREAS AND AREAS DIFFICULT TO VEGETATE
	CRUSHED STONE	SPREAD TO GREATER	USE IN SPECIFIC AREAS AS

16. APPLY LIMESTONE AND FERTILIZER ACCORDING TO SOIL TEST RECOMMENDATIONS. IF SOIL TESTING IS NOT FEASIBLE (CRITICAL TIME FRAMES OR VARIABLE SITES) THEN APPLY FERTILIZER AT A RATE OF 11 POUNDS PER 1,000 SF AND LIMESTONE AT A RATE OF 90 POUNDS PER 1,000 SF. FERTILIZER SHALL BE LOW PHOSPHATE (LESS THAN 2% PHOSPHORUS)

THAN 1/2" THICKNESS

- 17. CAUTION SHOULD BE TAKE WHEN THE PROPERTY IS LOCATED WITHIN 250 FEET OF A WATER BODY. IN THIS CASE ALL FERTILIZERS SHALL BE RESTRICTED TO A LOW PHOSPHATE. SLOW RELEASE NITROGEN FERTILIZER. SLOW RELEASE FERTILIZERS MUST BE AT LEAST 50% SLOW RELEASE NITROGEN COMPONENT. NO FERTILIZER EXCEPT LIMESTONE SHALL BE APPLIED WITHIN 25 FEET OF THE SURFACE WATER. THESE ARE REGULATED LIMITATIONS.
- 18. PERMANENT OR TEMPORARY COVER MUST BE IN PLACE BEFORE THE GROWING SEASON ENDS (SEE WINTER CONSTRUCTION NOTES). NO DISTURBED AREAS SHALL BE LEFT EXPOSED DURING THE WINTER MONTHS.
- 19. A VIGOROUS DUST CONTROL PROGRAM SHALL BE APPLIED BY THE SITE CONTRACTOR. DUST SHALL BE MANAGED THROUGH THE USE OF WATER AND/OR CALCIUM CHLORIDE.
- 20. IN NO WAY ARE THE MEASURES INDICATED ON THE PLANS OR IN THESE NOTES TO BE CONSIDERED ALL INCLUSIVE. THE CONTRACTOR SHALL USE JUDGMENT TO INSTALL ADDITIONAL EROSION CONTROL MEASURES AS SITE CONDITIONS, WEATHER OR CONSTRUCTION METHODS WARRANT
- 21. FOLLOWING PERMANENT STABILIZATION, TEMPORARY EROSION CONTROL MEASURES SHALL BE REMOVED AND ACCUMULATED SEDIMENTATION IS TO BE DISPOSED OF IN AN APPROVED LOCATION, OUTSIDE OF JURISDICTIONAL
- 22. LOT DISTURBANCE OTHER THAN SHOWN ON THE APPROVED PLANS, SHALL NOT COMMENCE UNTIL AFTER THE ROADWAY HAS THE BASE COURSE TO DESIGN ELEVATION AND THE ASSOCIATED DRAINAGE IS COMPLETE AND STABLE.
- 23. THE CONTRACTOR AND OWNER ARE RESPONSIBLE FOR OBSERVING AND MANAGING THE PROJECT PER RSA 430:53 AND AGR 3800 REGARDING INVASIVE SPECIES (PLANTS AND INSECTS). NO INVASIVE SPECIES PLANT OR INSECT SHALL BE INTRODUCED ONTO THE SITE.

**EROSION CONTROL NOTES** 



1. ALL PROPOSED VEGETATED AREAS WHICH DO NOT EXHIBIT A MINIMUM OF 85% VEGETATED GROWTH BY OCTOBER 15TH. OR WHICH ARE DISTURBED AFTER OCTOBER 15TH, SHALL BE STABILIZED. STABILIZATION METHODS SHALL INCLUDE SEEDING AND INSTALLING EROSION CONTROL BLANKETS ON SLOPES GREATER THAN 3:1, AND SEEDING AND PLACING 3 TO 4 TONS OF MULCH PER ACRE, SECURED WITH ANCHORED NETTING, ELSEWHERE. THE INSTALLATION OF EROSION CONTROL BLANKETS OR MULCH AND NETTING SHALL NOT OCCUR OVER ACCUMULATED SNOW OR FROZEN GROUND AND SHALL BE COMPLETED IN ADVANCE OF THAW OR SPRING MELT EVENTS.

2. ALL DITCHES OR SWALES WHICH DO NOT EXHIBIT A MINIMUM OF 85% VEGETATED GROWTH BY OCTOBER 15TH, OR WHICH ARE DISTURBED AFTER OCTOBER 15TH, SHALL BE STABILIZED WITH STONE OR EROSION CONTROL BLANKETS

3. AFTER NOVEMBER 15TH, INCOMPLETE ROAD OR PARKING SURFACES, WHERE WORK HAS STOPPED FOR THE WINTER SEASON, SHALL BE PROTECTED WITH A MINIMUM OF 3 INCHES OF CRUSHED GRAYEL OR PROPERLY INSTALLED EROSION CONTROL BLANKETS COVERED WITH HAY. OTHER STABILIZATION OPTIONS ARE TO BE APPROVED BY THE APPROPRIATE AGENCIES AND THE DESIGN ENGINEER. IF CONSTRUCTION IS TO CONTINUE THROUGH THE WINTER MONTHS THEN THE ROAD SHOULD BE CLEARED OF ACCUMULATED SNOW AFTER EACH STORM EVENT.


### WINTER CONSTRUCTION NOTES DT - 1

- 1. INSTALL SILTATION CONTROL FENCES IN LOCATIONS SHOWN HEREON. <u>EROSION AND SEDIMENTATION CONTROL</u> MEASURES SHALL BE INSTALLED PRIOR TO ANY EARTH MOVING OPERATION.
- 2. INSTALL STABILIZED CONSTRUCTION EXIT(S).
- 3. CUT AND CLEAR TREES; DISPOSE OF DEBRIS. STUMPS ARE TO BE REMOVED FROM THE SITE AND DISPOSED OF
- 4. REMOVE TOPSOIL AND STOCKPILE AWAY FROM ANY WETLAND. STABILIZE STOCKPILE IMMEDIATELY BY SEEDING. PLACE SILT FENCE AROUND THE DOWN SLOPE SIDE OF EARTH STOCKPILES.
- 5. ROUGH GRADE SITE CONSTRUCT DRAINAGE BASINS AND DRAINAGE SWALES DURING INITIAL PORTION OF CONSTRUCTION. STABILIZE IMMEDIATELY PER THE CONSTRUCTION AND EROSION CONTROL DETAILS. DO NOT DIRECT STORM WATER RUNOFF TO THESE STRUCTURES UNTIL A HEALTHY VEGETATIVE COVER IS ESTABLISHED.
- 6. BEGIN BUILDING CONSTRUCTION.

EROSION CONTROL NOTES).

- 7. CONSTRUCT GRAVEL PARKING AREA (PAVEMENT OPTIONAL) AND BUILDING PAD. INSTALL UTILITIES AND STRUCTURES. ALL CUT AND FILL SLOPES SHALL BE STABILIZED UPON COMPLETION OF ROUGH GRADING PER THE THE EROSION CONTROL NOTES.
- 8. INSPECT AND MAINTAIN EROSION CONTROL MEASURES ON A WEEKLY BASIS AND AFTER EVERY 0.25" OR GREATER
- 9. DAILY, OR AS REQUIRED, CONSTRUCT TEMPORARY BERMS, CULVERTS, DITCHES, SILTATION FENCES, SEDIMENT TRAPS, ETC. MULCH AND SEED AS REQUIRED.
- 10. FINISH GRADING TO PREPARE FOR PAVING (IF ANY) AND LOAMING. ALL DISTURBED AREAS SHALL BE STABILIZED WITHIN 72 HOURS AFTER FINAL CRADING.
- 11. FINISH PAVING (IF ANY). PERMANENT SEEDING SHALL BE PERFORMED UPON COMPLETION OF PARKING AREA (SEE
- 12. COMPLETE PERMANENT SEEDING AND LANDSCAPING.
- 13. TEMPORARY EROSION CONTROL MEASURES SHALL BE REMOVED WHEN ALL DISTURBED AREAS HAVE BEEN STABILIZED.
- 14. ALL STRUCTURES SHALL BE CLEANED OF SEDIMENTS ONCE CONSTRUCTION IS COMPLETE.

CONSTRUCTION SEQUENCE DT-1




- 1. DIMENSIONS GIVEN IN THIS DETAIL ARE EXAMPLES: DEVICE SHOULD BE INSTALLED PER MANUFACTURER'S SPECIFICATIONS.
- 2. INSTALL STRAW/COCONUT FIBER EROSION CONTROL MAT SUCH AS NORTH AMERICAN GREEN SC150BN OR EQUAL ON ALL SLOPES EXCEEDING 3' HORZ : 1' VERT.
- 3. THE EROSION CONTROL MATERIAL(S) SHALL BE ANCHORED WITH "U" SHAPED 11 GAUGE WIRE STAPLES OR WOODEN STAKES WITH A MINIMUM TOP WIDTH OF 1 INCH AND LENGTH OF 6 INCH.
- 4. SLOPE SURFACE SHALL BE FREE OF ROCKS, CLODS, STICKS AND GRASS. MATS / BLANKETS SHALL HAVE GOOD SOIL CONTACT.
- 6. BEGIN AT THE TOP OF THE SLOPE BY ANCHORING THE BLANKET AS SHOWN. ROLL THE BLANKETS DOWN THE SLOPE. ALL BLANKETS MUST BE SECURELY FASTENED TO SOIL SURFACE BY PLACING STAPLES OR STAKES IN APPROPRIATE LOCATIONS. REFER TO MANUFACTURERS STAPLE GUIDE FOR CORRECT STAPLE PATTERN.
- 7. LAY BLANKETS LOOSELY AND STAKE OR STAPLE TO MAINTAIN DIRECT CONTACT WITH THE SOIL DO NOT STRETCH.

5. APPLY UME, FERTILIZER AND PERMANENT SEEDING BEFORE PLACING BLANKETS.


- 8. IN LOOSE SOIL CONDITIONS THE USE OF STAPLES OR STAKE LENGTHS GREATER THAN 6 INCHES MAY BE NECESSARY TO PROPERLY SECURE THE BLANKETS.
- 9. THE CONTRACTOR SHALL MAINTAIN THE BLANKET UNTIL ALL WORK ON THE CONTRACT HAS BEEN COMPLETED AND ACCEPTED. MAINTENANCE SHALL CONSIST OF THE REPAIR OF AREAS WHERE DAMAGED BY ANY CAUSE. ALL DAMAGED AREAS SHALL BE REPAIRED TO REESTABLISH THE CONDITIONS AND GRADE OF THE SOIL PRIOR TO APPLICATION OF THE COVERING AND SHALL BE REFERTILIZED,
- 10. THERE SHALL BE NO PLASTIC, OR MULTI-FILAMENT OR MONOFILAMENT POLYPROPYLENE NETTING OR MESH WITH AN OPENING SIZE of greater than 1/8 inch material utilized.
- 11. TURF REINFORCEMENT MATS SHALL BE COVERED WITH SOIL TO PREVENT EXPOSURE OF THE MATS TO THE SURFACE.


EROSION BLANKETS - SLOPE INSTALLATION






# VIEW LOOKING UPSTREAM






# PROFILE - CHECK DAM SPACING

- 1. STONE CHECK DAMS SHOULD BE INSTALLED BEFORE RUNOFF IS DIRECTED TO THE SWALE OR
- 2. THE MAXIMUM CONTRIBUTING DRAINAGE AREA TO THE CHECK DAM SHOULD BE LESS THAN ONE ACRE.
- 3. STONE CHECK DAMS SHOULD NOT BE USED IN A FLOWING STREAM.
- 4. STONE CHECK DAMS SHOULD BE CONSTRUCTED OF WELL-GRADED ANGULAR 2 TO 3 INCH STONE. THE INSTALLATION OF 3/4-INCH STONE ON THE UPGRADIENT FACE IS RECOMMENDED FOR BETTER
- 5. WHEN INSTALLING STONE CHECK DAMS THE CONTRACTOR SHALL KEY THE STONE INTO THE CHANNEL BANKS AND EXTEND THE STONE BEYOND THE ABUTMENTS A MINIMUM OF 18-INCHES TO PREVENT
- 6. STONE CHECK DAMS SHOULD BE REMOVED ONCE THE SWALE OR DITCH HAS BEEN STABILIZED UNLESS OTHERWISE SPECIFIED.





PERSPECTIVE VIEW


SECTION VIEW NOTES:

1. SILT FENCES SHOULD NOT BE USED ACROSS STREAMS, CHANNELS, SWALES, DITCHES OR OTHER

- 2. SILT FENCE SHOULD BE INSTALLED FOLLOWING THE CONTOUR OF THE LAND AS CLOSELY AS
- POSSIBLE AND THE ENDS OF THE SILT FENCE SHOULD BE FLARED UPSLOPE. 3. IF THE SITE CONDITIONS INCLUDE FROZEN GROUND, LEDGE OR THE PRESENCE OF HEAVY ROOTS THE BASE OF THE FABRIC SHOULD BE EMBEDDED WITH A MINIMUM THICKNESS OF 8 INCHES OF 3/4-INCH
- 4. SILT FENCES PLACED AT THE TOE OF SLOPES SHOULD BE INSTALLED AT LEAST 6 FEET FROM THE TOE
- TO ALLOW SPACE FOR SHALLOW PONDING AND ACCESS FOR MAINTENANCE. 5. THE MAXIMUM SLOPE ABOVE THE FENCE SHOULD BE 2:1 AND THE MAXIMUM LENGTH OF SLOPE ABOVE
- THE FENCE SHOULD BE 100 FEET. 6. REMOVED SEDIMENT SHALL BE DEPOSITED TO AN AREA THAT WILL NOT CONTRIBUTE TO SEDIMENT
- 7. SILT FENCES SHOULD BE REMOVED WHEN THE UPSLOPE AREAS HAVE BEEN PERMANENTLY

SILT FENCE

OFF-SITE AND CAN BE PERMANENTLY STABILIZED.



NOTES:

- 1. THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION THAT WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHT-OF-WAYS. THIS MAY REQUIRE TOP DRESSING, REPAIR AND/OR CLEANOUT OF ANY MEASURES USED TO TRAP SEDIMENT.
- 2. THE MINIMUM STONE USED SHOULD BE 3-INCH CRUSHED STONE.
- 3. THE MINIMUM LENGTH OF THE PAD SHOULD BE 75 FEET, EXCEPT THAT THE MINIMUM LENGTH MAY BE REDUCED TO 50 FEET IF A 3-INCH TO 6-INCH HIGH BERM IS INSTALLED AT THE ENTRANCE OF THE PROJECT SITE.
- 4. THE PAD SHOULD EXTEND THE FULL WIDTH OF THE CONSTRUCTION ACCESS ROAD OR 10 FEET, WHICHEVER IS

PLAN VIEW

- 5. THE PAD SHOULD SLOPE AWAY FROM THE EXISTING ROADWAY.
- 6. THE PAD SHOULD BE AT LEAST 6-INCHES THICK.
- 7. THE GEOTEXTILE FILTER FABRIC SHOULD BE PLACED BETWEEN THE STONE PAD AND THE EARTH SURFACE BELOW
- 8. THE PAD SHALL BE MAINTAINED OR REPLACED WHEN MUD AND SOIL PARTICLES CLOG THE VOIDS IN THE STONE SUCH THAT MUD AND SOIL PARTICLES ARE TRACKED OFF-SITE.
- 9. NATURAL DRAINAGE THAT CROSSES THE LOCATION OF THE STONE PAD SHOULD BE INTERCEPTED AND PIPED BENEATH THE PAD, AS NECESSARY, WITH SUITABLE OUTLET PROTECTION.
- 10. WHEN NECESSARY, WHEELS SHALL BE CLEANED PRIOR TO ENTRANCE ONTO PUBLIC RIGHT-OF-WAY.
- 11. WHEN WASHING IS REQUIRED, IT SHALL BE DONE ON AN AREA STABILIZED WITH CRUSHED STONE THAT DRAINS INTO AN APPROVED SEDIMENT TRAP OR SEDIMENT BASIN. SCALE: N.T.S.

**GRAVEL CONSTRUCTION EXIT** 



12/15/22 EROS. CONTROL BLANKET NOTES PER AOT RMI JEN CEB C/O DR CK REV. DATE DESCRIPTION

> **EROSION CONTROL DETAILS TAX MAP 249 LOT 16** (HALL ROAD)

CANTERBURY, NEW HAMPSHIRE PREPARED FOR:

PATRIOT HOLDINGS, LLC 4007 DEAN MARTIN DRIVE LAS VEGAS, NV 89103-4138

Surveying  $\phi$  Engineering  $\phi$  Land Planning  $\phi$  Permitting  $\phi$  Septic Designs

SCALE: NOT TO SCALE MAY 24, 2022



LAND CONSULTANTS, PLLC


206 Elm Street, Milford, NH 03055 Phone: (603) 672-5456 Fax: (603) 413-5456 www.FieldstoneLandConsultants.com

PROJ. NO. 3127.01

SHEET:

PAGE NO. 7 OF 9

DT - 1



- 2. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE LOCATION, SIZE, AND ELEVATION OF ALL EXISTING UTILITIES SHOWN OR NOT SHOWN ON THESE PLANS AND SHALL VERIFY THAT ALL THE INFORMATION SHOWN HEREON IS CONSISTENT, COMPLETE, ACCURATE, AND CAN BE CONSTRUCTED PRIOR TO AND/OR DURING CONSTRUCTION. FIELDSTONE LAND CONSULTANTS, PLLC, AS THE DESIGN ENGINEER, SHALL BE NOTIFIED IN WRITING OF ANY DISCREPANCIES, ERRORS, OMISSIONS, OR EXISTING UTILITIES FOUND INTERFERING WITH THE PROPOSED CONSTRUCTION SO THAT REMEDIAL ACTION MAY BE TAKEN BEFORE PROCEEDING WITH THE WORK.
- 3. THE CONTRACTOR SHALL CONTACT "DIGSAFE" 72 HOURS PRIOR TO THE START OF CONSTRUCTION (1-800-255-4977 IN NH, 1-888-344-7233 IN MA).
- 4. COMPLIANCE WITH ALL APPLICABLE REGULATIONS AND SPECIAL CONDITIONS OF TOWN/CITY AGENCIES, SUCH AS THE PLANNING BOARD, ZONING BOARD, CONSERVATION COMMISSION, AND OTHERS, IS MANDATORY AND IS THE RESPONSIBILITY OF THE OWNER.
- 5. ANY ALTERATION OF THIS DESIGN OR CHANGE DURING CONSTRUCTION MAY REQUIRE APPROVAL OF VARIOUS TOWN/CITY BOARDS OR AGENCIES AND SHALL BE DISCUSSED WITH THE OWNER AND FIELDSTONE LAND CONSULTANTS, PLLC PRIOR TO CONSTRUCTION.
- 6. THE CONTRACTOR IS RESPONSIBLE FOR CONTACTING THE APPROPRIATE CITY DEPARTMENTS PRIOR TO CONSTRUCTION TO ARRANGE FOR NECESSARY INSPECTIONS.
- 7. THE CONTRACTOR IS RESPONSIBLE FOR MAINTAINING ACCURATE AS-BUILT INFORMATION OF ALL WORK, ESPECIALLY UNDERGROUND CONSTRUCTION OF UTILITY LINES, SERVICES, CONNECTIONS, ETC. AND APPROPRIATE TIES TO ABOVE GROUND PERMANENT STRUCTURES, FIELD SURVEY COORDINATES, OR SOME OTHER METHOD OF ESTABLISHING THE AS-BUILT CONDITION OF ALL CONSTRUCTION.
- 8. THE CONTRACTOR AND OWNER ARE RESPONSIBLE FOR OBSERVING AND MANAGING THE PROJECT PER RSA 430:53 AND AGR 3800 REGARDING INVASIVE SPECIES (PLANTS AND INSECTS). NO INVASIVE SPECIES PLANT OR INSECT SHALL BE INTRODUCED ONTO THE SITE.


DT-2

DT-2

DT-2


branch date and the branch of the branch of







THE BINDER COURSE SHALL BE PLACED IMMEDIATELY AFTER TRENCH CONSTRUCTION AND ALLOWED TO STAND A MINIMUM OF 90 DAYS. A LEVELING COURSE SHALL BE APPLIED OVER THE TRENCH AFTER 90 DAYS AND THE ENTIRE ROAD OVERLAID TO THE LIMITS SHOWN ON THE PLANS.






PAVEMENT SECTION










2 FT.

UNPAVED AREAS


ALL








EMERGENCY SPILLWAY DETAIL




CULVERT	HEADWALL	HEADWALL	FILL	TOP	HEADWALL
DIAM.	LENGTH	HEIGHT	HEIGHT	HEIGHT	воттом
D	L	Н	FH	h	WIDTH W
INCHES	FEET & INCHES				
12	4'-3"	3'-9"	1'-1"	1'-3"	1'-11.25"
15	6,-0,,	4'-3"	1'-7"	1'-6"	2'-0.75"
18	7'-0"	4'-6"	1'-10"	1'-6"	2'-1.50"
24	9,-0 <b>,</b>	5'-0"	2'-4"	1'-6"	2'-3.00"


HEADWALL - PRECAST CONCRETE (HW1)


HEADWALL SHALL BE STEEL REINFORCED AND CONFORM TO NHDOT STANDARD PLAN HW-2, LAST REVISED JUNE 16, 2010.



DECIDUOUS TREE PLANTING DETAIL







**CONSTRUCTION DETAILS** 

TAX MAP 249 LOT 16
(HALL ROAD)
CANTERBURY, NEW HAMPSHIRE
PREPARED FOR:

# PATRIOT HOLDINGS, LLC 4007 DEAN MARTIN DRIVE LAS VEGAS, NV 89103-4138

SCALE: NOT TO SCALE

MAY 24, 2022


Surveying 

Engineering 

Land Planning 

Permitting 

Septic Designs



206 Elm Street, Milford, NH 03055
Phone: (603) 672-5456 Fax: (603) 413-5456

Www.FieldstoneLandConsultants.com

FILE: 3127DT01.dwg PROJ. NO. 3127.01 SHEET: DT-2 PAGE NO. 8 OF 9


CONTACT DIG SAFE
72 HOURS PRIOR
TO CONSTRUCTION


DIGSAFE.COM


OR DIAL 8 I I


IT'S SMART. IT'S FREE. IT'S THE LAW.


DT-2
















**CONSTRUCTION DETAILS** 

**TAX MAP 249 LOT 16** (HALL ROAD) CANTERBURY, NEW HAMPSHIRE PREPARED FOR:

# PATRIOT HOLDINGS, LLC 4007 DEAN MARTIN DRIVE LAS VEGAS, NV 89103-4138

MAY 24, 2022 SCALE: NOT TO SCALE

Surveying ♦ Engineering ♦ Land Planning ♦ Permitting ♦ Septic Designs



LAND CONSULTANTS, PLLC

206 Elm Street, Milford, NH 03055 Phone: (603) 672-5456 Fax: (603) 413-5456 www.FieldstoneLandConsultants.com

SHEET: DT-3

- 6" LAYER OF COURSE SAND OR 3/8" PEA GRAVEL; - GRASS TURF WITH A HIGH INFILTRATION RATE (HIGH SAND CONTENT) THAT CAN BE INUNDATED FOR OVER 72 HOURS;

4. ONCE EXCAVATED AND PRIOR TO FILLING, THE UNDERLYING SOILS SHALL BE DEEPLY TILLED WITH A ROTARY TILLER OR DISC HARROW TO RESTORE INFILTRATION RATES, FOLLOWED BY A

5. THE BASIN FLOOR OF INFILTRATION BASINS IB1 & IB2 SHALL BE PREPARED USING ONE OF

1. REMOVE ALL ORGANIC MATERIAL FROM AREA BELOW PROPOSED INFILTRATION BASINS AND

2. CARE SHALL BE TAKEN TO PROTECT THE UNDERLYING SOILS FROM CONSTRUCTION TRAFFIC

3. DO NOT TRAFFIC EXPOSED SOIL SURFACE WITH CONSTRUCTION EQUIPMENT. IF FEASIBLE, PERFORM EXCAVATIONS WITH EQUIPMENT POSITIONED OUTSIDE THE LIMITS OF THE

INFILTRATION BASIN CONSTRUCTION NOTES

TO EXPOSE UNDERLYING SOILS.

PASS WITH LEVELING DRAG.

THE FOLLOWING METHODS:

AND THE DISCHARGE OF SEDIMENT LADEN RUNOFF.

- COARSE ORGANIC MATERIAL SUCH AS AN EROSION CONTROL MIX OR COMPOSTED MULCH THAT IS TILLED INTO THE SOIL , SOAKED, AND ALLOWED TO DRY.

6. DO NOT PLACE INFILTRATION BASINS/TRENCHES INTO SERVICE UNTIL ALL CONTRIBUTING AREAS HAVE BEEN FULLY STABILIZED.